



14 HILLSIDE AVENUE LLC 65.52-1-17 S 74°29'29" W IRON PIPE 70.70 -U-POLES WALL 0.3'± EAST OF LINE ASPHALT DRIVE 6" PERF. PVC\_ SDR OR EQUAL STORY FRAMED AVENUE N/F TAX MAP #65.52-1-5 LIBER-606 PAGE-497 SURVEY: S 72°09'44" W 67.19' (DEED: S 73°13'00" S 67.36') LIBER-6456 PAGE-198 TAX MAP #65.52-1-6 PFISTER 65.52-1-17 HILLSIDE CONC.
HEADWALL N 73°13'00" E 45.25' N/F WEISSBERG & FERRANTE 65.52 - 1 - 17

N/F

SURVEY PROVIDED BY W.E. JAMES ENGINEERING AND LAND SURVEYING, PLLC LICENSE # 050506 PROPOSED RETAINING WALL PLAN SCALE: 1"=2'



SECTION 1-1: MAX STRENGTH GABION WALL SECTION SCALE: 1"=2'



DRAWING	No.		TITLE			
DRAWING	1		RETAINING	WALL PL	AN &	DETAILS
DRAWING	2	_	NOTES &	SPECIFICA	ATIONS	S

9,218 SQ.FT.

TAX MAP REFERENCE: TOWN OF ORANGETOWN TAX MAP SECTION 65.52, BLOCK 1, LOT 5 & 6

THE EDUCATION LAW OF THE STATE OF NEW YORK PROHIBITS ANY PERSON ALTERING ANYTHING ON THESE DRAWINGS AND/OR THE ACCOMPANYING SPECIFICATIONS, UNLESS IT IS UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER. WHERE SUCH ALTERATIONS ARE MADE, THE PROFESSIONAL ENGINEER MUST SIGN, SEAL, DATE AND DESCRIBE THE FULL EXTENT OF THE ALTERATION ON THE DRAWINGS AND/OR IN THE SPECIFICATIONS. (NYS EDUCATION LAW SECTION 7209-2)

N.Y.S. P.E. LIC. NO. 101473

DRAWN BY:

TOWN OF ORANGETOWN ROCKLAND COUNTY, NEW YORK

**DIDIER ARANGO** 

PLANNING SOARD MEETING C.

MAY 1 0 2313

Town Of Orangetown

REVISED WALL SECTION

REVISED WALL DESIGN

DESCRIPTION

Web: www.ANZNY.com

RETAINING WALL PLAN & DETAILS

CHECKED BY: VR DATE: MARCH 09, 2022 SCALE: 1 IN. = 20 FT. PROJECT NO: DRAWING NO:

DROP OF CURB BOTTOM OF WALL PROPOSED GABION RETAINING WALL - PROPOSED PERFORATED PIPE

**LEGEND** 

----- EXISTING 2' CONTOUR

--- -- 360-- -- EXISTING 10' CONTOUR

W ——— EXISTING WATERLINE

= = = = Existing storm drain line

--- s - - s - - s - - s - - EXISTING SEWER LINE

EXISTING STONEWALL

СВ

+ 360.0

-O- UP

EXISTING FIRE HYDRANT

EXISTING CATCH BASIN

EXISTING SEWER MANHOLE

EXISTING SPOT ELEVATION

EXISTING UTILITY POLE

EXISTING GAS LINE

**EXISTING CONDITION** SCALE: 1"=2"

DATED NOVEMBER 5, 2020.

UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY FROM AVAILABLE INFORMATION. THE CONTRACTOR SHALL CALL THE LOCAL UNDERGROUND FACILITIES PROTECTIVE ORGANIZATION TO HAVE ALL UNDERGROUND UTILITIES MARKED IN THE FIELD PRIOR TO ANY CLEARING OR ANY CONSTRUCTION. THE CONTRACTOR SHALL ALSO VERIFY THE LOCATION, SIZE, AND INVERT OF ALL UTILITIES PRIOR TO ANY CONSTRUCTION. ANY UTILITY FOR WHICH NO EVIDENCE CAN BE SEEN ON THE SURFACE OF THE LANDS MAY NOT BE SHOWN ON THIS DRAWING.

ATZL, NASHER & ZIGLER P.C ENGINEERS-SURVEYORS-PLANNERS 232 North Main Street **OWNER & ADDRESS:** New City, New York 10956 DIDIER ARANGO 18 HILLSIDE AVENUE Tel: (845) 634-4694 NYACK, NY 10960 Fax: (845) 634-5543 AREA: E-mail: info@anzny.com

MAR 6 2023

2 01-28-23

REVISION DATE

PROJECT:

12-5-22

- 2. THE OWNER SHALL BE RESPONSIBLE FOR ALL TEMPORARY PERMITS, CONNECTION PERMITS. FEES, INSPECTIONS AND RECORD KEEPING REQUIRED BY ALL MUNICIPAL, UTILITY, HEALTH, ENVIRONMENTAL, STATE OR FEDERAL AGENCIES THAT MAY HAVE JURISDICTION. FURTHERMORE. THE OWNER SHALL BE RESPONSIBLE TO MEET OR EXCEED ALL REQUIREMENTS OF THE AGENCIES OR AUTHORITIES HAVING JURISDICTION OVER HIS WORK. ALL CONFLICTS IN REQUIREMENTS OF DIFFERENT AGENCIES, AUTHORITIES AND/OR THE DESIGN SHALL BE BROUGHT TO THE ATTENTION OF THE OWNERS' REPRESENTATIVE BEFORE PROCEEDING.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE TO LOCATE AND MAINTAIN THE PROPERTY AND PROJECT LIMITS THROUGH OUT THE PROJECT. ALL CONFLICTS BETWEEN THE DESIGN AND THE PROJECT / PROPERTY LIMITS SHALL BE BROUGHT TO THE ATTENTION OF THE OWNER'S REPRESENTATIVE BEFORE PROCEEDING. UNLESS DESCRIBED IN THE CONTRACT DOCUMENTS OR SHOWN ON THE DRAWINGS THE OWNER HAS NOT SECURED ANY RIGHT OF WAYS, EASEMENTS OR AGREEMENTS WITH OTHER PROPERTY OWNERS OR PROPERTY USERS. THEREFORE IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO SECURE AND MAINTAIN ANY TEMPORARY RIGHT OF WAYS, EASEMENTS, PERMITS OR AGREEMENTS HE MAY NEED TO PERFORM HIS WORK. ALL SUCH AGREEMENTS SHALL HOLD THE OWNER, ENGINEER AND HIS AGENTS HARMLESS AND IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO BEAR ALL COSTS. THE CONTRACTOR SHALL COPY THE OWNER ON RELEASES OF ALL AGREEMENTS PRIOR TO FINAL PAYMENT BY THE OWNER TO THE CONTRACTOR.
- 4. UNLESS OTHERWISE NOTED ON THE DRAWINGS OR IN THE CONTRACT DOCUMENTS THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION SURVEY, LAYOUT AND RECORD DRAWINGS FOR THIS CONTRACT. ANY CONFLICTS IN SURVEY/LAYOUT AND THE DESIGN OR AGENCIES REQUIREMENTS SHALL BE BROUGHT TO THE ATTENTION OF THE OWNER'S REPRESENTATIVE PRIOR TO PROCEEDING WITH THE WORK. THE CONTRACTOR SHALL PROTECT AND SAFEGUARD ALL EXISTING SURVEY MONUMENTS, CONTROL AND TIE-DOWNS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COST ASSOCIATED WITH ERRORS IN THE STAKE-OUT AND LOCATION OF HIS WORK. THE CONTRACTOR SHALL PAY ALL COSTS TO REPAIR OR REPLACE DAMAGED SURVEY MONUMENTS, CONTROL AND TIE-DOWNS.
- 5. 5. NO CHANGES TO THE DESIGN OR MATERIALS SPECIFIED MAY BE MADE WITHOUT WRITTEN AUTHORIZATION BY THE ENGINEER OR IN THE CASE OF UTILITIES OR ROAD WORK TO BE DEDICATED, THE AUTHORITY RECEIVING DEDICATION. THE CONTRACTOR SHALL PROVIDE TO THE OWNER AT THE END OF THE CONTRACT A RECORD SET OF DRAWING REFLECTING ALL CHANGES MADE BY THE CONTRACTOR DURING CONSTRUCTION.
- 6. EROSION CONTROL IS NECESSARY WHEN SEDIMENT, DUST, EROSION, OR CONTAMINATED RUN-OFF MAY OCCUR. THE CONTRACTOR SHALL BE RESPONSIBLE TO PLACE AND MAINTAIN EROSION CONTROL OR RUN-OFF PROTECTIONAS REQUIRED TO PROTECT HIS WORK, THE WORK OF HIS SUBCONTRACTORS, OR OTHER PARTIES ASSOCIATED WITH THE PROJECT, ADJACENT PROPERTIES AND THE HEALTH AND WELL BEING OF THE WORKERS, PUBLIC AND SURROUNDING NATURAL RESOURCES. THE CONTRACTOR SHALL BE FAMILIAR WITH ALL FEDERAL, STATE AND LOCAL REQUIREMENTS REGARDING EROSION AND RUN-OFF CONTROL AND SHALL SIGN A CERTIFICATION STATEMENT INDICATING THAT HE UNDERSTANDS AND WILL COMPLY WITH THE SITE'S STORM WATER POLLUTION PREVENTION PLAN IF ONE WAS PREPARED FOR THE
- 7. THE CONTRACTOR SHALL BE FAMILIAR WITH THE PROJECT SITE AND ALL ADJACENT PEDESTRIAN, TRAFFIC AND BUSINESS USES. THE CONTRACTOR SHALL TAKE WHAT EVER PRECAUTIONS AND STEPS NECESSARY TO MAINTAIN SAFETY AND OPERATION OF THESE USES IN ACCORDANCE WITH FEDERAL, STATE, COUNTY AND LOCAL REQUIREMENTS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COSTS AND DAMAGES CAUSED FROM HIS FAILURE TO TAKE PROPER AND ADEQUATE PRECAUTIONS. THE CONTRACTOR SHALL BE FAMILIAR WITH ALL FEDERAL, STATE AND LOCAL REQUIREMENTS REGARDING THESE USES INCLUDING BUT NOT LIMITED TO THE MAINTENANCE AND PROTECTION OF TRAFFIC REQUIRED BY THE NEW YORK STATE DEPARTMENT OF TRANSPORTATION (NYS D.O.T.) AND CORRESPONDING TOWN.
- 8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COSTS AND DELAYS ASSOCIATED WITH WEATHER, GROUNDWATER, AND OTHER OCCURRENCES THAT COULD BE EXPECTED OR ARE COMMON WITH THIS TYPE WORK. THE CONTRACTOR SHALL REVIEW ALL PERTINENT DOCUMENTS INCLUDING SOILS REPORTS, SOILS BORINGS AND OTHER SOIL OR SITE DATA.
- 9. THE CONTRACTOR SHALL BE RESPONSIBLE TO SAVE AND PROTECT HIS WORK THROUGH OUT THE CONTRACT. ANY DAMAGES REQUIRING REPAIRS OR REPLACEMENT SHALL BE CORRECTED BY THE CONTRACTOR AT HIS EXPENSE.
- 10. WHEN WORK IS DONE WITHIN A ROAD, UTILITY OR PRIVATE EASEMENT, RIGHT OF WAY OR OTHER PROPERTY AGREEMENT THE CONTRACTOR SHALL DO ALL WORK WITHIN THAT AREA PER THE AUTHORITY HAVING JURISDICTION.
- 11. ALL EXISTING UTILITIES ARE SHOWN PER SURFACE SURVEYS AND/OR RECORD MAPS AND MAY VARY FROM ACTUAL IN FIELD LOCATIONS. THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY STAKE OUTS AND LOCATING UTILITIES PRIOR TO COMMENCING WORK. ANY DAMAGE TO UTILITIES DUE TO IMPROPER STAKE OUT, LACK OF STAKE OUT OR THE FAILURE TO VERIFY DIFFERENCES BETWEEN DRAWINGS AND ACTUAL FIELD CONDITIONS WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO REPAIR, REPLACE OR PAY DAMAGES AT NO EXPENSE TO THE CONTRACT.
- 12. CONTRACTOR SHALL FURNISH AND APPLY WATER AND/OR CALCIUM CHLORIDE AS NECESSARY TO CORRECT DUSTY CONDITIONS RESULTING FROM LOCAL TRAFFIC ON THE STREET OR CONTRACTORS OPERATIONS.

## EARTHWORK

- 1. PRIOR TO STARTING ANY CUTS OR FILLS THE CONTRACTOR SHALL STRIP AND STOCKPILE ALL TOPSOIL. STRIPPING OF TOPSOIL CAN ONLY COMMENCE AFTER THE CLEAR AND GRUB OPERATIONS ARE COMPLETE IN THAT AREA. TOPSOIL SHALL BE STOCKPILED IN AREAS DESIGNATED ON THE PLANS OR APPROVED BY THE OWNER'S REPRESENTATIVE. THE CONTRACTOR SHALL REVIEW THE SOILS REPORTS, BORING LOGS AND WHEN NECESSARY HIS OWN FIELD VERIFICATION SO AS TO BE FAMILIAR WITH THE DEPTH OF TOPSOIL. THE CONTRACTOR SHALL TAKE ALL REASONABLE PRECAUTIONS TO PREVENT OVER AND UNDER REMOVAL OF TOPSOIL.
- 2. UNLESS OTHERWISE NOTED ON THE DRAWINGS OR IN THE CONTRACT DOCUMENTS THE CONTRACTOR SHALL RETAIN AND PAY ALL COST FOR SOIL COMPACTING TESTING TO BE PERFORMED BY AN INDEPENDENT TESTING LABORATORY. TESTING FOR COMPACTION SHALL BE DONE EVERY 2000 SQ. FT. EACH LIFT. IN TRENCHES COMPACTION TESTING SHALL BE DONE EVERY 100 LF. EVERY OTHER LIFT, BUT NOT LESS THAN 1 TEST EVERY OTHER LIFT.
- 3. COMPACTION REQUIREMENTS SHALL BE THOSE OUTLINED IN THE PLAN. IF THE PLAN IS NOT CLEAR OR DOES NOT GIVE REQUIREMENTS THE FOLLOWING WILL BE USED. THE SUBGRADE SOILS AND BACK FILL AREA SHALL BE COMPACTED TO A MINIMUM OF 95% MAXIMUM DRY DENSITY PER ASTM 01557 (MODIFIED PROCTOR). ALL LANDSCAPE AND LAWN AREAS SHALL BE COMPACTED TO 90% MAXIMUM DRY DENSITY PER ASTM 01557 (MODIFIED PROCTOR). THE TESTING LAB SHALL TEST SOILS IN ACCORDANCE WITH ASTM 02922 (NUCLEAR METHOD) WITH PROCTORS FOR EACH SOIL TYPE.
- 4. UNLESS OTHERWISE NOTED IN THE SOILS REPORT OR ON THE DRAWINGS THE ON SITE MATERIAL SHALL BE USED TO MAKE FILLS. ALL MATERIAL TO BE USED FOR FILL SHALL BE FREE OF ORGANICS, FROZEN MATERIAL, CONTAMINATED MATERIAL, DEBRIS AND ANY ROCKS LARGER THAN 4 INCHES. FOR FILL PLACED WITHIN 1 FOOT OF SUBGRADE NO ROCK SHALL BE GREATER THAN 2 INCHES IN DIAMETER. THE CONTRACTOR SHALL BEAR ALL COST ASSOCIATED WITH DRYING, SEGREGATING OR OTHER REQUIRED METHODS TO TREAT SOILS TO MEET COMPACTION AND OTHER REQUIREMENTS.
- 5. BACKFILLS SHALL BE PLACED IN LIFTS NOT TO EXCEED 8 INCH.
- 6. IF IMPORTED MATERIAL IS REQUIRED THE SOURCE AND A RANDOM COMPOSITE SAMPLE SHALL BE REVIEWED BY THE TESTING LABORATORY PRIOR TO BEING BROUGHT TO SITE. IMPORTED MATERIAL SHALL HAVE 100% PASSING THE 3 INCH SIEVE FOR FILL UP TO 1 FOOT OF SUBGRADE AND 100% PASSING THE 2 INCH SIEVE FOR FILLS WITHIN 1 FOOT OF SUBGRADE. THE IMPORTED MATERIAL SHALL HAVE NO MORE THAN 40% PASSING THE NO. 40 SIEVE AND 15% PASSING THE NO. 200 SIEVE. WAIVERS TO THESE REQUIREMENTS CAN ONLY BE GIVEN JOINTLY BY THE OWNER AND THE GEOTECHNICAL ENGINEER THAT PREPARED THE SOILS REPORT.
- 7. THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PROTECT EARTHWORK OPERATIONS FROM WEATHER AND GROUND WATER INCLUDING KEEPING POSITIVE DRAINAGE. DIVERT DRAINAGE, DEWATERING AND SEALING DISTURBED AREAS WITH A STEEL DRUM ROLLER PRIOR TO INCLEMENT WEATHER.
- 8. ALL FINAL SUBGRADE UNDER PROPOSED PAVEMENT, BUILDING OR OTHER STRUCTURE SHALL BE PROOF ROLLED AS DESCRIBED ABOVE FOR IDENTIFYING OF SOFT AREAS. AREAS FOUND TO BE UNACCEPTABLE SHALL BE SCARIFIED, DRIED AND RECOMPACTED. RETEST BY PROOF ROLL AS NECESSARY.
- 9. ALL EXCAVATIONS SHALL MAINTAIN SAFE SIDE SLOPES IN ACCORDANCE WITH LOCAL, STATE AND OSHA REQUIREMENTS. NO STOCKING OF MATERIAL CLOSE TO AN OPEN CUT OR STEEP SLOPE WILL BE PERMITTED IN AN EFFORT TO PREVENT CAVE-INS.
- 10. TRENCH EXCAVATIONS SHALL BE MADE UNIFORM AS SHOWN ON PLAN. NO MORE TRENCH SHALL BE OPEN IN ONE DAY THAN CAN BE PROPERLY BACKFILLED IN THAT SAME DAY TO MINIMIZE WEATHER AND SAFETY CONCERNS. COMPACTION REQUIREMENTS ARE NOT RELIEVED IN THESE AREAS AND WILL REMAIN AS STATED ON THE DRAWINGS OR ABOVE.
- 11. IF ROCK IS ENCOUNTERED THAT WAS NOT INDICATED ON THE PLANS OR SOILS REPORT, THE CONTRACTOR SHALL INFORM THE OWNER / ENGINEER OF THE RECORD FOR ALTERNATIVE DESIGN. NO ROCK EXCAVATION IS EXPECTED.
- 12. WHERE ROCK IS ADJACENT TO A STRUCTURE OR UTILITY THE ROCK SHALL BE REMOVED TO A MINIMUM OF 6 INCHES BELOW AND 1 TIMES THE DIAMETER BUT NOT LESS THAN 1 FOOT OR GREATER THAN 3 FEET ON ANY SIDE OF THE UTILITY OR STRUCTURE.
- 13. NO EXPLOSIVES WILL BE ALLOWED. NO BLASTING IS ALLOWED AT THIS PROJECT SIDE.
- 14. UNLESS OTHERWISE NOTED ON THE PLANS, THE CONTRACTOR SHALL REMOVE ALL EXCESS TOPSOIL, CUT MATERIAL OR WASTE FROM SITE AND DISPOSE OF IN A LEGAL
- 15. CONTRACTOR SHALL PROVIDE TEMPORARY SUPPORT STRUCTURE FOR EXCAVATION AS REQUIRED.
- 16. CONTRCTOR SHALL PROTECT ALL UNDERGROUND PIPES AND FACILITIES, INCLUDING UTILITY AND STORMWATER PIPES AND CATCH BASINS THROUGHOUT EXCAVATION AND CONSTRUCTION. ANY DAMAGE TO THE ABOVEMENTIONED FACILITIES SHALL BE REPAIRED AT CONTRACTOR'S COST.

INTERLOCKING WIRE FASTENER

OVERLAPPING RING WIRE FASTENER ALTERNATE TYING FASTENERS

## **GABION WALL NOTES:**

- 1. THE SCOPE OF WORK SHALL CONSIST OF FURNISHING; ASSEMBLING AND INSTALLING ROCK FILLED WIRE MESH GABION BASKETS.
- 2. GABIONS SHALL BE FABRICATED, ASSEMBLED AND INSTALLED IN ACCORDANCE WITH THE NOMINAL WIRE SIZES AND DIMENSIONS FOUND IN TABLES 1, USING THE FOLLOWING
- 3. WIRE FOR FABRICATION AND ASSEMBLY SHALL BE HOT-DIP GALVANIZED. THE WIRE SHALL HAVE A MINIMUM TENSILE STRENGTH OF 60,000 PSI. GALVANIZED STEEL WIRE SHALL CONFORM TO ASTM A 641, CLASS 3, AND SOFT TEMPER.
- 4. ALTERNATE FASTENERS FOR USE WITH WIRE MESH GABIONS, SUCH AS RING FASTENERS. SHALL BE FORMED FROM WIRE MEETING THE SAME QUALITY AND COATING THICKNESS REQUIREMENTS AS SPECIFIED FOR THE GABIONS.
- 5. STANDARD FASTENERS AND ALTERNATE FASTENERS MUST PROVIDE A MINIMUM STRENGTH OF 1,400 LBS. PER LINEAL FOOT FOR GABION BASKETS AND 9000 LBS. PER LINEAL FOOT FOR GABION MATTRESSES. WHEN USED TO INTERCONNECT GABION BASKETS OR MATTRESSES WITH PVC COATING, RING FASTENERS SHALL BE MADE OF STAINLESS STEEL AND SPIRAL FASTENERS SHALL BE PVC COATED.
- 6. ROCK SHALL CONFORM TO THE QUALITY REQUIREMENTS AS FOLLOWS AND AT LEAST 85 PERCENT IF THE ROCK PARTICLES, BY WEIGHT, SHALL BE WITHIN THE PREDOMINANT ROCK SIZE RANGE. RECYCLED CONCRETE MAY BE USED IN LIEU OF THE SPECIFIED AGGREGATE AT THE ENGINEER'S DISCRETION.

G	ABION BASKET	PREDOMINANT	MINIMUM ROCK	MAXIMUM ROCK
	HEIGHT	ROCK SIZE	DIMENSION	DIMENSION
	(INCHES)	(INCHES)	(INCHES)	(INCHES)
BASKET	12" 「 18" 36"	4 TO 8	4	8

- 7. THE FOUNDATION ON WHICH THE GABIONS ARE TO BE PLACED SHALL BE CUT OR FILLED AND GRADED TO THE LINES AND GRADES SHOWN ON THE DRAWINGS.
- 8. SURFACE IRREGULARITIES, LOOSE MATERIAL, VEGETATION, AND ALL FOREIGN MATTER

SHALL BE REMOVED FROM FOUNDATION SURFACE AREA.

- 9. WHEN FILL IS REQUIRED, IT SHALL CONSIST OF MATERIALS CONFORMING TO THE SPECIFIED
- 10. GABIONS AND BEDDING OR SPECIFIED GEOTEXTILES SHALL NOT BE PLACED UNTIL THE FOUNDATION PREPARATION IS COMPLETED, AND THE SUBGRADE SURFACES HAVE BEEN
- 11. COMPACTION BEDDING OR FILTER MATERIAL WILL BE REQUIRED PER PLANS AND SPECIFICATIONS.

INSPECTED AND APPROVED BY THE ENGINEER'S REPRESENTATIVE.

- 12. THE SURFACE OF THE FINISHED MATERIAL SHALL BE TO GRADE AND FREE OF MOUNDS, DIPS OR WINDROWS. EXTRA CARE SHOULD BE TAKEN WITH FOUNDATION PREPARATIONS IN ORDER TO ENSURE A LEVEL AND SMOOTH SURFACE.
- 13. THE ASSEMBLY AND PLACEMENT OF GABIONS SHALL BE IN ACCORDANCE WITH THE FOLLOWING PROCEDURES:
- 14. ASSEMBLY. ROTATE THE GABION PANELS IN TO POSITION AND JOIN THE VERTICAL EDGES WITH FASTENERS FOR GABION ASSEMBLY. WHERE LACING WIRE IS USED, WRAP THE WIRE

## GENERAL RETAINING WALL NOTES


- 1. WALL CONSTRUCTION SHALL BE SUPERVISED BY A QUALIFIED ENGINEER OR TECHNICIAN TO VERIFY FIELD AND SITE SOIL CONDITIONS. IF THIS WORK IS NOT PERFORMED BY THE SITE GEOTECHNICAL ENGINEER, A QUALIFIED GEOTECHNICAL ENGINEER/TECHINICIAN SHALL BE CONSULTED IN THOSE MATTERS PERTAINING TO THE SOIL CONDITIONS AND
- 2. THE FOUNDATION SOILS AT THE BASE OF THE WALL(S) SHALL BE INSPECTED BY THE ENGINEER. ANY UNSUITABLE SOILS OR IMPROPERLY COMPACTED EMBANKMENT MATERIAL SHALL BE REMOVED AND REPLACED AS DIRECTED BY THE ENGINEER PRIOR TO WALL CONSTRUCTION TO PROVIDE ADEQUATE BEARING CAPACITY AND MINIMIZE SETTLEMENT.
- 3. ALL WALL EXCAVATION AND RETAINED SOILS SHALL BE INSPECTED FOR GROUNDWATER CONDITIONS. ANY ADDITIONAL DRAINAGE PROVISIONS REQUIRED IN THE FIELD SHALL BE INCORPORATED INTO THE WALL CONSTRUCTION AS DIRECTED BY THE GEOTECHNICAL
- 4. ALL SOIL BACKFILL SHALL BE TESTED BY THE ENGINEER FOR MOISTURE, DENSITY, AND COMPACTION PERIODICALLY (EVERY 2' VERTICALLY, 100'-200' C/C) MEETING THE MINIMUM REQUIREMENTS OF THE APPROVED DESIGN PLANS OR SPECIFICATIONS.
- 5. ALL WALL ELEVATIONS, GRADES, AND BACKSLOPE CONDITIONS SHALL BE VERIFIED BY THE ENGINEER IN THE FIELD FOR CONFORMANCE WITH APPROVED DESIGN PLANS. ANY REVISIONS TO THE STRUCTURE GEOMETRY OR DESIGN CRITERIA SHALL REQUIRE DESIGN MODIFICATIONS PRIOR TO PROCEEDING WITH CONSTRUCTION.
- 6. DURING WALL CONSTRUCTION, PERIODIC INSPECTION SHALL BE CONDUCTED FROM START TO COMPLETION, AND CERTIFIED THAT THE WALL HAS BEEN CONSTRUCTED IN ACCORDANCE WITH THE DESIGN BY A REGISTERED LICENSED PROFESSIONAL ENGINEER IN THE STATE OF NEW YORK.

# INSPECTION AND CERTIFICATION NOTES

- A. ANY PROPOSED RETAINING WALLS SHALL BE DESIGNED AND INSPECTED DURING CONSTRUCTION, AND CERTIFIED THAT THAY HAVE BEEN CONSTRUCTED IN ACCORDANCE WITH THE DESIGN BY A REGISTERED PROFESSIONAL ENGINEER IN THE STATE OF NEW YORK.
- B. TOP OF RETAINING WALL SHALL MATCH PROPOSED GRADE.
- 1) CONTRACTOR TO CONTACT ALL INVOLVED AGENCIES PRIOR TO EXCAVATION.
- 2) IF REQUIRED, THE CONTRACTOR TO OBTAIN BUILDING PERMIT FROM THE APPROPRIATE GOVERNING AUTHORITY.
- 3) MINIMUM INSPECTIONS ARE AS FOLLOWS: A) FOOTING INSPECTION
- B) MID HEIGHT INSPECTION C) FINAL INSPECTION
- CRIMPED END OF JOINT

WITH ALTERNATING SINGLE AND DOUBLE HALF HITCHES AT INTERVALS BETWEEN FOUR (4) TO FIVE (5) INCHES, WHERE SPIRAL FASTENERS ARE USED, CRIMP THE ENDS TO SECURE THE SPIRALS IN PLACE. WHERE RING TYPE ALTERNATE FASTENERS ARE USED FOR BASKET ASSEMBLY, INSTALL THE FASTENERS AT A MAXIMUM SPACING OF 6 INCHES. USE THE SAME FASTENING PORCEDUREX TO INSTALL INTERIOR DIAPHRAGMS WHERE THEY ARE REQUIRED.

- 15. INTERIOR DIAPHRAGMS WILL BE REQUIRED WHERE ANY INSIDE DIMENSIONS EXCEEDS THREE (3) FEET FOR GABION BASKETS THICKER THAN 12". DIAPHRAGMS WILL BE INSTALLED TO ASSURE THAT NO OPEN INTERVALS EXCEEDS THREE (3) FEET. FOR BASKETS 12" OR LESS RECTANGULAR CELLS ARE ALLOWED WITH DIMENSIONS 36" IN ONE DIRECTION AND NOT TO EXCEED 72" IN THE PERPENDICULAR DIRECTION.
- 16. PLACEMENT, PLACE THE EMPTY GABIONS ON THE FOUNDATION AND INTERCONNECT THE ADJACENT GABIONS ALONG THE TOP, BOTTOM, AND VERTICAL EDGES USING LACING WIRE OR SPIRALS. WRAP THE WIRE WITH ALTERNATING SINGLE AND DOUBLE HALF HITCHES AT INTERVALS BETWEEN FOUR (4) TO SIX (6) INCHES. SPIRAL FASTENERS ARE COMMONLY USED FOR THE ASSEMBLY AND INTERCONNECTION OF WELDED MESH GABIONS. SPIRALS ARE SCREWED DOWN AT THE CONNECTING EDGES THEN EACH END OF THE SPIRAL IS CRIMPED TO SECURE IT IN PLACE. LACING MAY BE USED AS NEEDED TO SUPPLEMENT THE INTERCONNECTION OF WELDED MESH GABIONS, ADN THE CLOSING OF LIDS.
- 17. INTERCONNECT EACH LAYER OF GABIONS TO THE UNDERLYING LAYER OF GABIONS ALONG THE FRONT, BACK, AND SIDES. STAGGER THE VERTICAL JOINTS BETWEEN THE GABIONS OF ADJACENT ROWS AND LAYER BY AT LEAST ONE-HALF OF A CELL LENGTH.
- 18. FILLING OPERATION:
- 19. AFTER ADJACENT EMPTY WIRE GABION UNITS ARE SET INLINE AND GRADE AND COMMON SIDES PROPERLY CONNECTED, THEY SHALL BE PLACED IN STRAIGHT-LINE TENSION TO GAIN A UNIFORM ALIGNMENT. STAKING OF THE GABIONS MAY BE DONE TO MAINTAIN THE ESTABLISHED PROPER ALIGNMENT PRIOR TO THE PLACEMENT OF THE ROCK. NO TEMPORARY SSTAKES SHALL BE PLACED THROUGH GEOTEXTILE MATERIAL. CONNECTING LACING WIRE AND OTHER FASTENERS (AS ALLOWED) SHALL BE ATTACHED DURING THE FILLING OPERATION TO PRESERVE THE STRENGTH AND SHAPE OF THE STRUCTURE.
- 20. INTERNAL CONNECTING CROSS-TILE WIRES SHALL BE PLACED IN EACH UNRESTRAINED GABION CELL GREATER THAN 18 INCHES IN HEIGHT, INCLUDING GABION CELLS LEFT TEMPORARILY UNRESTRAINED. TWO INTERNAL CONNECTING WIRES SHALL BE PLACED CONCURRENTLY WITH ROCK PLACEMENT, AT EACH 12-INCH INTERVAL OF DEPTH.
- 21. IN WELDED MESH GABIONS THESE CROSSTIES OR STIFFENERS WILL BE PLACED ACROSS THE CORNERS OF THE GABIONS (AT 12 INCHES FROM THE CORNERS) PROVIDING DIAGONAL BRACING. LACING WIRE OR PREFORMED WIRE STIFFENERS MAY BE USED.
- 22. THE GABIONS SHALL BE CAREFULLY FILLED WITH ROCKS, EITHER BY MACHINE OR HAND METHODS, ENSURING ALIGNMENT, AVOIDING BULGES, AND PROVIDING A COMPACT MASS THAT MINIMIZES VOIDS. AT NO POINT IN THE FILLING PROCESS MAY ROCK BE MECHANICALLY PLACED FROM A HEIGHT OF OVER 36" FROM MACHINE TO FILL AREA. MACHINE PLACEMENT WILL REQUIRE SUPPLEMENTING WITH HANDWORK TO ENSURE THE DESIRED RESULTS. THE CELLS IN ANY ROW SHALL BE FILLED IN STAGES SO THAT THE DEPTH OF ROCK PLACED IN ANY ONE CELL DOES NOT EXCEED THE DEPTH OF ROCK IN ANY ADJOINING CELL BY MORE THAN 12 INCHES. ALONG THE EXPOSED FACES, THE OUTER LAYER OF STONE SHALL BE CAREFULLY PLACED AND ARRANGED BY HAND TO ENSURE A NEAT, COMPACT PLACEMENT WITH A UNIFORM APPEARANCE.



TYPICAL ASSEMBLED GABION BASKET

- 23. THE LAST LAYER OF ROCK SHALL BE UNIFORMLY LEVELED TO THE TOP EDGES OF GABIONS. LIDS SHALL BE PLACED OVER THE ROCK FILLING USING ONLY APPROVED LID CLOSING TOOLS AS NECESSARY. THE USE OF CROWBARS OR OTHER SINGLE POINT LEVERAGE BARS FOR LID CLOSING IS PROHIBITED DUE TO THE POTENTIAL FOR DAMAGE
- 24. THE GABION LID SHALL THEN BE SECURED TO THE SIDES, ENDS, AND DIAPHRAGMS WITH SPIRAL BINDERS, APPROVED ALTERNATE FASTENERS, OR LACING WIRE WRAPPED WITH ALTERNATING SINGLE AND DOUBLE HALF-HITCHES IN THE MESH OPENINGS.
- 25. ANY DAMAGE TO THE WIRE OR COATINGS DURING ASSEMBLY, PLACEMENT AND FILLING SHALL BE REPAIRED PROMPTLY IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS OR REPLACED WITH UNDAMAGED GABION BASKETS.

TABLE 1 (MINIMUM REQUIREMENTS) GABION BASKETS - HEIGHT 12, 18, OR 36 INCHES, LENGTH AS SPECIFIED

TYPE OF WIRE	MESH SIZE (INCHES)	WIRE DIAMETER (INCHES)	PVC COATING (INCHES)	TOTAL DIAMETER (INCHES)	GALVANIZED COATING OZ./SF
LACING WIRE		0.086	0.02	0.126	0.70
WELDED MESH	3 X 3	0.118	NONE	0.118	0.80
WELDED MESH	3 X 3	0.105	0.02	0.145	0.80
SPIRAL BINDER		0.105	0.02	0.145	0.80

## **DESIGN PARAMETERS**

### SOIL AND DESIGN PARAMETERS

A. THE FOLLOWING SOIL PARAMETERS, HAVE BEEN USED FOR THE PREPARATION OF THE FINAL DESIGN:

#### **DESIGN PARAMETERS\***

<u>SOIL</u>	SOIL UNIT WEIGHT (PCF)	INTERNAL FRICTION ANGLE (Ø)
BACKFILL	125	27.0
FOUNDATION SOIL	125	27.0
APPLIED SURCHARGE L	OADING=40 PSF (SNOW LOAD	) · · · · · · · · · · · · · · · · · · ·

\* SOIL PARAMETERS CONERVATIVELY ASSUMED FOR DESIGN

MINIMUM FACTORS C	F SAFETY	PROVIDED FACTORS	OF SAFE
OVERTURNING	2.0	OVERTURNING	2.5
SLIDING	1.5	SLIDING	2.1
BEARING CAPACITY	2.0	BEARING CAPACITY	2.1


SHOULD THE ACTUAL SOIL CONDITIONS OBSERVED DURING CONSTRUCTION DIFFER FROM THOSE ASSUMED FOR THE DESIGN, DESIGN SHALL BE REVIEWED BY THE WALL DESIGN ENGINEER AT THE OWNER'S GEOTECHNICAL ENGINEER'S DIRECTION.

01-28-23


REVISION DATE

PROJECT:

12-5-22



TYPICAL INSTALLATION GABION BASKETS



ATZL, NASHER & ZIGLER P.C ENGINEERS-SURVEYORS-PLANNERS 232 North Main Street New City, New York 10956 Tel: (845) 634-4694 Fax: (845) 634-5543

REVISED WALL SECTION

REVISED WALL DESIGN

DESCRIPTION

E-mail: info@anzny.com

Web: www.ANZNY.com

DIDIER ARANGO

TOWN OF ORANGETOWN ROCKLAND COUNTY, NEW YORK

**NOTES & SPECIFICATIONS** 

DRAWN BY: CHECKED BY: VR DATE: MARCH 09, 2022 SCALE: AS SHOWN PROJECT NO: DRAWING NO: 4998

UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY FROM AVAILABLE INFORMATION. THE CONTRACTOR SHALL CALL THE LOCAL UNDERGROUND FACILITIES PROTECTIVE RGANIZATION TO HAVE ALL UNDERGROUND UTILITIES MARKED THE FIELD PRIOR TO ANY CLEARING OR ANY CONSTRUCTION

CRIMPED END -- C

OF JOINT